

County of San Diego Central Avenue Flood Control Improvement Project

Update # 14
June 11, 2007

1 Two-Week Look Ahead



*** Milestone ***
The project is now 50% complete!

During the weeks of **June 11th and June 18th**, the contractor will perform the following daytime operations:

- Continue constructing the reinforced concrete box (RCB) north of Central Avenue.
- Begin constructing falsework for the top slab of the RCB.
- Begin constructing the channel maintenance ramp and concrete slope protection south of Central Avenue.
- Continue grading the channel between Dawsonia Street and Central Avenue.
- Begin installing pre-cast concrete cellular blocks, used for slope stabilization, at the west end of the project area.
- Continue maintaining and installing sediment and erosion control measures throughout the project.

Temporary Traffic Control

Central Avenue will remain open during construction. Flagging operations may be in effect between the hours of 8:30 am - 2:30 pm. For your safety and to avoid double penalty traffic fines, please allow extra time to travel through the construction zone.

General Work Hours

Monday - Friday: 7:00 am - dusk or 7:00 pm, whichever is earlier.

2 Construction Impacts

During construction, dump trucks, concrete trucks and heavy equipment will be entering and exiting the work area, as well as crossing Central Avenue. For your safety, please slow down and use caution when travelling through the construction site.

The center left-turn lane on Central Avenue has been eliminated to accommodate construction for the remaining two cells of the triple-chamber RCB culvert north of Central Avenue. The lane reconfiguration for this phase is estimated to last through July 2007.

The creek flow was successfully diverted into the newly constructed cell of the RCB.

Please observe the posted speed limit of 25 mph.

3 Project Description

From November 2006 through Fall of 2007, the County will construct flood control improvements on Central Avenue, between Dawsonia Street and Belle Bonnie Brae Road. The project includes the following improvements:

- A three-chamber concrete box culvert along the north side of Central Avenue.
- A 1000-foot long flood wall on the north side of the channel between Central Avenue and Dawsonia Street.
- A 200-foot long flood wall on the south side of the channel by Dawsonia Street.
- Installation of fiber matting and plantable concrete cells.

Errecas, Inc. is the contractor for this \$5.9 million construction project. The project is funded by the County of San Diego and the Federal Emergency Management Agency.

4 For More Information

Thank you for your cooperation and patience as we work to improve your community. If you have any questions, comments or concerns about this project or if you would like to receive project updates please contact:

Leslie Emmanuel

Email: LeslieE@CollaborativeServices.biz

Questions? Call 1-619-232-2640

